

Performance Specification

Project Name: Augustana Chilled Water Project Unit Tag: CH-2 Qty.: 1 Model: YLAA0155SJ17XF

Full Load - Design

	PIN							
YLAA0155SJ	17XFBBCTXA	SXBLXCXX44	XE1XXXHXXX	YAXGXXX7XX	XVGNXXXXXX			
510	520	530	540	550	560	570	580	590

Unit						
Model No.	YLAA0155SJ17XFB					
Number of Compressors	5					
Compressor Type	Scroll - Hermetic					
Number of Compressor Circuits	2					
Refrigerant	R454B					
Performa	nce Data					
Cooling Capacity [tons.R]	135.5					
Total Power Input [kW]	178.6					
EER [Btu/W.h]	9.102					
NPLV.IP [Btu/W.h]	16.98					
A-Weighted Sound Power [dB(A)]	97.0					
Electrical Data						
Nominal Voltage / Voltage Limits	200-208/3/60 / 180-220					
Compressor RLA (each circuit) [A]	106.2 / 106.2 / 106.2 / 106.2 / 106.2 / -					
High LRA Current (each circuit) [A]	652.0 / 652.0 / 652.0 / 652.0 / 652.0 / -					
Fan QTY (each circuit)	4/4					
Fan FLA (each circuit) [A]	7.6 / 7.6					
Min. Circuit Ampacity [A]	628.0					
Recommended Fuse / CB Rating [A]	700.0					
Max. Inverse Time CB Rating [A]	700.0					
Max. Dual Element Fuse Size [A]	700.0					
Unit Short Circuit Withstand [kA]	65 kA					
Wires Per Phase	3 + 2					
Wire Range (Lug Size)	#2/0 AWG - 400 kcmil + 250 - 500 kcmil					
Compressor kW	165.1					



Page 1 of 4

Performance Impacting Options						
Starter Type	Across the line starter					
Power Factor Correction Cap	acitor No Power Capacitor required					
Remote Evaporator	Standard Cooler required					
Sound Kit	No Acoustic Blanket required					
Fan	Low Sound Fans with VSD					
Weight & Dimensional Data						
Shipping Weight [lbs]	7198					
Operating Weight [lbs]	7306					
Refrigerant Charge [lbs]	122					
Length [in]	187.7					
Width [in]	88.3					
Height [in]	94.2					

Project Name: Augustana Chilled Water Project Rating Engine Version: REV.v9_17.idd

Rating Engine Version: REV.v9_17.idd Version: SN23.10 Generated: 2023/11/14 at 12:55
Unit Name: Unit 2 Version: CHL.2023-10.001 Page 1 of 4



Performance Specification

Project Name: Augustana Chilled Water Project Unit Tag: CH-2 Qty.: 1 Model: YLAA0155SJ17XF

Heat Exchanger Performance						
Evapo	orator	Condenser	Condenser (Air Cooled)			
Heat Exchanger Type Plate Heat Exchanger		Ambient Air Temperature* [°F]	95.0			
Entering Fluid Temperature* [°F]	54.00	Altitude* [ft]	5400			
Leaving Fluid Temperature* [°F]	44.00	Condensing Temperature [°F]	130.43 / 121.10			
Flow Rate [USGPM]	341.7	Number of Fans	4/4			
Fouling Factor* [h ft2 F/Btu]	0.000100	Total Air Flow [cfm]	120000			
Fluid Type* / Concentration* [%]	Propylene Glycol / 35.0	Total Fan Power [kW]	13.44			
Fluid Volume [USGAL]	13.2					
Evaporating Temperature [°F]	37.35					
Evaporator Pressure Drop [ft H2O]	14.4					
Strainer Pressure Drop [ft H2O]	3.07					
Extension Kit Pressure Drop [ft H2O]	7.11					
Total Pressure Drop [ft H2O]	24.5					
Fluid Connection Diameter [in]	4					
Minimum Flow Rate [USGPM]	150.0					
Maximum Flow Rate [USGPM]	625.0					

^{*} Designates user specified input

Certified in accordance with the AHRI Air-Cooled Water-Chilling Packages Certification Program, which is based on AHRI Standard 550/590 (I-P) and AHRI Standard 551/591 (SI). Certified units may be found in the AHRI Directory at www.ahridirectory.org. Unit contains freeze protection fluids in the evaporator with a leaving chilled fluid temperature above 32 DEG F [0 DEG C] and is certified when rated per the Standard with water.



Generated: 2023/11/14 at 12:55

Page 2 of 4

Part Load Performance (Based on Standard AHRI Unloading)							
Percent Load	Ambient [°F]	Capacity [tons.R]	Power Input [kW]	Unit Efficiency [Btu/W.h]			
100.0	95.0	135.5	178.6	9.102			
91.7	80.1	124.3	114.2	13.05			
68.5	80.1	92.78	81.84	13.60			
50.6	65.1	68.51	42.97	19.13			
23.9	65.1	32.42	20.55	18.93			
25.2	55.0	34.19	18.71	21.94			
25.2	55.0	34.19	18.71	21.94			

Project Name: Augustana Chilled Water Project

Rating Engine Version: REV.v9_17.idd

Version: SN23.10 Unit Name: Unit 2 Version: CHL.2023-10.001 Page 2 of 4



Page 3 of 4

Generated: 2023/11/14 at 12:55

Performance Specification

Project Name: Augustana Chilled Water Project Unit Tag: CH-2 Qty.: 1 Model: YLAA0155SJ17XF

	Sound Power Levels (In Accordance with AHRI 370)									
Percent Load Ambier		Octave Band Center Frequency [Hz]							LIMA	
	Ambient [*F]	63	125	250	500	1000	2000	4000	8000	LWA
100.0	95.0	99.0	98.0	94.0	95.0	92.0	88.0	85.0	82.0	97.0
91.7	80.1	98.0	96.0	93.0	93.0	90.0	87.0	83.0	81.0	95.0
68.5	80.1	94.0	93.0	89.0	90.0	88.0	84.0	81.0	78.0	92.0
50.6	65.1	90.0	89.0	85.0	86.0	85.0	81.0	78.0	76.0	89.0
23.9	65.1	85.0	83.0	80.0	82.0	81.0	78.0	74.0	72.0	85.0
25.2	55.0	85.0	83.0	80.0	82.0	81.0	78.0	74.0	72.0	85.0
25.2	55.0	85.0	83.0	80.0	82.0	81.0	78.0	74.0	72.0	85.0

Note: Unit is equipped with Low Sound Fans with VSD.

Measurement of sound pressure used to obtain the sound power data presented is based on AHRI-370.

Air-cooled chillers are rated in terms of sound power not sound pressure. Johnson Controls provides estimates of sound pressure, but this is not the rating metric.

For an air-cooled chiller, sound pressure calculated from sound power varies depending on how the chiller is assumed to behave, i.e. the radiation model. In other words, determining sound pressure from sound power requires making assumptions that result in different answers at a given distance from the chiller. The environment also influences sound pressure in the field installation. Sound pressure estimation radiation models pertaining to aircooled chillers include the 'traditional' hemispherical model, parallelepiped model and equivalent hemispherical model.

Regarding sound power, Johnson Controls references tolerance limits based on ASHRAE guidelines. These are +/- 6dB in the 63Hz octave band, +/-4dB in all other octave bands and +/- 3dB for the overall dBA.

Tolerance limits are based on uncertainties associated with:

- 1. Measurement Test Procedure
- 2. Repeatability
- 3. Production / Manufacturing Variability

Standard deviation associated with air-cooled chiller sound data is a measure of spread i.e. it indicates the range of probability of sound levels. Note that for operating conditions other than AHRI's Standard Rating Condition, higher levels of uncertainty can be expected.

Lead times for factory performance testing depend on test laboratory availability. Please confirm with Johnson Controls Customer Service.

Performance at AHRI Conditions						
Evap	prator	Condenser				
EFT [°F]	54.00	Ambient Temp. [°F]	95.0			
LFT [°F]	44.00	Altitude [ft] 0.00				
Flow Rate [USGPM] 341.7		Performance				
Pressure Drop [ft H2O]	11.9	EER [Btu/W.h] 9.932				
Fluid Type	Water	IPLV.IP [Btu/W.h]	17.75			
Fouling Factor [h ft2 F/Btu]	0.000100	Net Cooling Capacity [tons.R]	143.2			
Fluid Volume [USGAL]	13.2					

Note: Unit rated at design condition capacity.

Project Name: Augustana Chilled Water Project Rating Engine Version: REV.v9_17.idd

Version: SN23.10 Page 3 of 4 Unit Name: Unit 2 Version: CHL.2023-10.001



Performance Specification

Project Name: Augustana Chilled Water Project Unit Tag: CH-2 Qty.: 1 Model: YLAA0155SJ17XF

	Part Load Performance (Based on AHRI 550/590 - 2018 (IP))							
Percent Load	Ambient [°F]	Capacity [tons.R]	Power Input [kW]	Unit Efficiency [Btu/W.h]				
100.0	95.0	143.2	173.0	9.932				
90.4	80.0	129.4	110.8	14.02				
66.9	80.0	95.79	79.36	14.48				
73.0	65.0	104.5	68.69	18.26				
48.5	65.0	69.46	41.92	19.89				
51.2	55.0	73.24	38.50	22.83				
24.2	55.0	34.63	18.26	22.76				

Notes:

Country of Origin:Mexico

Min flow rate is for chillers using water. For glycol chillers please contact the application engineering team.

This unit does not have a coil coating selected.

Compliant with ASHRAE 90.1 - 2010,2013,2016,2019,2022.

Compliant with IECC - 2012,2015,2018.

Compliant with the requirements of the LEED Energy and Atmosphere Enhanced Refrigerant Management Credit (EAc4).

The product image shown is for illustrative purposes only and is not representative of selected options.

Project Name: Augustana Chilled Water Project

Rating Engine Version: REV.v9_17.idd Unit Name: Unit 2 Version: SN23.10 Version: CHL.2023-10.001 Generated: 2023/11/14 at 12:55

Page 4 of 4

Page 4 of 4